

Pre-installation Checklist

Conditions for installation:

	1	 The ambie 	nt temperat	ure:5 - 35 °C,	and the re	lative humidit	y:≤ 85%.
--	---	-------------------------------	-------------	----------------	------------	----------------	----------

Reserve locations for one air switch and one three-core socket.

- The laboratory should be free of violent vibration, airflow, strong electromagnetism and corrosive gases.
- Equip the laboratory with proper work surface: 700mm (W)×2000 mm(L)×600mm(H).
- Equip the laboratory with stable power supply of 220 V ± 22 V / 50 ± 1 Hz (grounded well). Heating power ≤ 1.5 kW.

Preparation:

- Dryer: Silica gel, 1 Bottle.
- 2. Absorbent cotton (medical).
- Standard coal samples in which all kinds of moisture content are contained. 3.
- Prepare one desicator.